

ADDENDUM NO. 1
For RFP #8291
HIGH CALCIUM QUICKLIME

The following changes are amended for RFP #8291 – High Calcium Quicklime as follows:

1. *Page 3:* **Question Deadline** has been extended from August 16, 2018. The new deadline for questions is now 3:00 p.m. on Tuesday, August 21, 2018.
2. *Page 16:* **Calcium Oxide (CaO) & Silica (SiO₂) content** – These chemical requirements have been revised as follows, “The Quicklime shall be **90%** (~~92%~~) **available** CaO as a minimum and shall contain no more than **1.8%** (~~1.7%~~) SiO₂ in composition.”
3. *Page 17:* **Slaking Rate** – The minimum temperature rise has been revised from 54 degree C downward to 50 degree C as follows, “The minimum temperature rise, after three minutes or less on slaking, shall be **50** (~~54~~) degree C and the reaction shall be completed within ten minutes.”
4. *Page 17:* **Produce Acceptance** – It is acceptable for the certificate of product analysis (COA) be for the railcar containing the bulk shipment.
5. *Page 17:* **Deliveries** – Additional physical information is being provided for the lime facility as follows, “ There is only one (1) unloading station with two (2) unloading panels and associated unloading hose connections, one (1) for each silo. The height from the unloading hose connection to the top of the two lime silos is approximately 66 feet. The unloading hose length to the two silos are approximately 90 feet (for the silo near the unloading area) and 120 feet. Each unloading hose has three (3) reinforced 90 degree elbows.”
6. *Page 31:* **Contractor License Certification** requirement has been removed from the RFP. Please delete this page altogether.

Thank you,



Tamblynn Stewart
Senior Contract Service Officer
Sacramento Regional County Sanitation District

August 15, 2018

RFP #8291